

Project Planning & Control

Lesson 3

Two-Span Bridge: Activity Identification and Duration Estimation (Cont.,)

Koshy Varghese, Ph.D.

Professor

Building Technology & Construction Management

Department of Civil Engineering

I.I.T. Madras




Learning Objectives

- General activities & operations for the two-span bridge exercise
- Initial estimate of duration of activities based on operation details
- Establishing predecessor relationships


*This example is only for classroom discussion
Intent is to illustrate some of the aspects to be considered for time planning.
It is not a comprehensive procedure.*

Two Span Bridge- Example



Recall Discussion on Activities identified in Lecture -3

Two Span Bridge



1. Order & Deliver Piles
2. Cast Beams
3. Drive Piles East
4. Const East Pile Cap
5. Const E. Abutment
6. Drive Piles Centre
7. Const Centre Pile Cap
8. Const Centre Pier

9. Drive Piles West
10. Const West Pile Cap
11. Const W. Abutment
12. Place Beams E. Span
13. Place Beams W. Span
14. Deck Slab East
15. Deck Slab West
16. Lay Roads

1. Order & Deliver Piles



Casting Operation



Stored Piles

1. Order & Deliver Piles - Duration

Standard sizes of prefabricated piles are available.

No. Piles required is say *East* (4x3) + *Center* (2x3) + *West* (4x3) = 30

When should Order be placed ?

Find Lead time for delivery. (Stock availability, Delivery to location)

What if the piles were cast on site ?

Casting Yard Set-up 10 days

No. piles required (4x3) + (2x3) + (4x3)

Operation Sequence:

1.0 Reinforcement Fabrication – 1 day

2.0 Casting Pile

2.1 Formwork Assembly – 1 day

2.2 Concrete pouring – ½ day

2.3 Form removal after – 1 day

2.4 Form removal time- ½ day

Curing before usage – 21 days regular

2 days steam curing

Production Rate vs. based on No. Forms

1 1 pile in 3 days -> 90 days for 30 piles

2 2 piles in 3 days -> 45 days “

3 3 piles in 3 days -> 30 days “

What determines production rate ?

2. Cast Beams



Casting Operation



Transport



2. Cast Beams - Duration

Beams are prefabricated in casting yard set-up on site.

No. Beams required is say *3 for each span- total = 6*

No. beams required = 3 + 3

Operation Sequence:

1.0 Reinforcement Fabrication – 2 days

2.0 Casting Beam

2.1 Formwork Assembly – 1 day

2.2 Concrete pouring – 1 day

2.3 Form removal after – 1 day

2.4 Form removal time- 1 day

**Curing before usage – 28 (14) days regular
3 days steam curing**

Assume reinforcement fabrication is
done in parallel

Production Rate – based on No. Forms/Beds

No. Sets of forms

1 1 beam in 4 days -> 24 days for 6 beams

2 2 beams in 4 days -> 12 days “

3 3 beams in 4 days -> 8 days “

What production rate is required ?

Assume 3 sets of forms:

Total Duration= 2 +14 (1st set);
Day 6+14 (2nd set)?